BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18418/CALL-2

APPROVED SCHEDULE - B

E/B P/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Pot Hole Filling and Road patch work in Kogilu, Kogilu Layout, Agrahara, Agrahara layout, Kattigenahalli palanahalli, Vinayakanagara, Dwarakanagra and other areas in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B B UMESHA		
				In Figures		In Words
1	1536.3	KSRRB- M 3000-2: Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per s[ecifications. MORTH Specification No. 3003 (Page No. 265/ Item No.35.20	Sqm	21.6	33184.08	Rupees Twenty One and Sixty Paise Only
2	230.45	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2013-14	Cum	1645.0	379090.25	Rupees One Thousand Six Hundred Forty Five Only
3	1542.9	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification	Sqm	368.0	567787.20	Rupees Three Hundred Sixty Eight Only
					980061.53	

B.B.

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/8/16

25/08